

## Toe Protection to Seawall, Cliff Parade, Walton on the Naze

Coast protection works have recently been completed on a section of seawall below Cliff Parade, Walton on the Naze.

The works consisted of reinforcing the seawall toe with a relatively new material called “Elastocoast”.



Approximately 130 metres of the seawall has now been treated where serious erosion often occurs during the severe winter storms. The reinforcing consists of forming a 3 metre wide wedge of Elastocoast material below normal beach level to seal the lowest section of the seawall against undermining by storm tides.

The project was managed by Technical and Procurement Services on behalf of the Technical Services Portfolio Holder, and is funded from Tendring District Council’s coast protection budget.

The contractor for this work was [Hesselberg Hydro](#) of Lyminge, Kent

If you would like to find out more about Elastocoast please click on this link [Information on Elastocoast](#)