

Extension to Open Stone Asphalt Revetment, West End, Dovercourt

Coast protection works have been completed to reinforce the clay bank around the southern end of the public open space off the end of West End Lane, Dovercourt.

The improvements were necessary as the end of the existing open stone asphalt revetment was suffering erosion and the adjacent clay bank was at risk.



[West End, Dovercourt location map](#)

The work consisted of reinforcing approximately 130 metres of the existing clay bank defence with an overlay of open stone asphalt.

The revetment construction commenced on 3rd December 2007 and was completed by the 15th December 2007. A new set of beach access steps will be constructed as soon as practicable after completion of the revetment work.

The project has been managed by Technical and Procurement Services on behalf of the Technical Services Portfolio Holder, and is funded from Tendring District Council's coast protection budget.

Our contractor for this work was Hesselberg Hydro of Lyminge, Kent
<http://www.hesselberg-hydro.com/>